Multimodal Construction Intelligence Platform
Safety audits, crack diagnostics, cost and valuation, and weather-aware site protocols.

Safety & PPE | Crack diagnostics | Planning & valuation | Site assistant

Weather-aware daily advisory

Today's conditions

○ Normal ○ High Wind ◉ Heavy Rain ○ Extreme Heat

Electrical hazard: isolate temporary power, check RCCB/ELCB, keep cables off wet ground.

Do not pour concrete; cover fresh work with tarpaulin.

Pump out excavations; check shoring for collapse risk.

Anti-slip measures on ramps and walkways.

Site engineering assistant

Ask about curing, mix design, cracks, PPE, costs...

2000 sqft ghar me kitna steel lagega?

Weather Note: Heavy rain on site today—ensure all stacked steel reinforcement is elevated off

muddy ground on timber sleepers and covered with tarpaulins to prevent flash rusting. Check electrical panels and cable joints for water ingress before restarting any work.

For a 2000 sqft residential house (G+1 or independent floors) constructed with RCC framed structure:

- **Average Steel Requirement: 3.5 to 4.5 kg per sqft** (as per IS 456 / good engineering practice).
- **Total Area:** 2000 sqft
- **Total Steel Required: 7,000 kg to 9,000 kg (7 to 9 tonnes)**.

Breakdown by Structural Element:

1. **Foundations (Footings & Pedestals):** ~15-20%
2. **Columns & Beams:** ~40-45%
3. **Slabs & Staircase:** ~30-35%
4. **Lintels & Chajjas:** ~5-10%

Cost Estimation (Approximate):

- At current market rates (Fe500D grade branded TMT like Tata Tiscon, Jindal Panther, etc. @ approx. ₹60,000 to ₹65,000 per metric tonne including GST):
- **Total Steel Cost: ₹4,20,000 to ₹5,85,000 (INR)**.

⚠️ **On-Site Verification Required:** *This is a thumb-rule estimate. The exact tonnage depends on your structural consultant's detailed bar bending schedule (BBS), soil bearing capacity (foundation type), seismic zone (IS 1893), and clear spans. Have your site engineer verify the final BBS before placing the purchase order.*

Clear conversation